

RELATED EXPERIENCE

CITY OF PONTIAC NORTH SAGINAW STREET RECONSTRUCTION

Johnson & Anderson was retained by the City of Pontiac to provide road design services for .91 miles of North Saginaw Street from Montcalm to Woodward Avenue, in accordance with MDOT standards. Golder Associates is contracted to perform geotechnical engineering services.

Location:	City of Pontiac
Construction Date:	2015
Construction Cost:	\$1,382,000
Client:	City of Pontiac Department of Engineering
Contact:	Mr. John Balint, P.E. (248) 785-3615

The project consists of removing the existing concrete pavement and reconstructing with base repair, new concrete pavement with a center turn lane, curb and gutter, and drainage improvements.

J&A coordinated with the State Historic Preservation Office (SHPO) since there was a historical marker within the project limits on the Southeast quadrant of Fairgrove/Clark

Street.

J&A is also contracted by the Oakland County Water Resources Commissioner's Office to perform preliminary and final design services and permitting for over 3,200 LF of water supply improvements along North Saginaw Street during the road reconstruction.

This project was funded in part by the Surface Transportation Urban Local (STUL) federal program.

This project is slated to be completed later this Summer.